


Company- NATURAL GAS AND OIL COMPANY
 Farm- Larrison "A" No. 1

SEC. 35 T. 29 R. 13W
 NW NW NW

35-29-13W
 County Pratt

KANSAS



Total Depth. 4616'
 Comm. 5-2-58 Comp. 5-19-58
 Shot or Treated.
 Contractor. Graham-Michaelis Drilling Co.
 Issued. 9-27-58

Elevation. 1827 RB

Production. 37 BOPD

CASING:

10 3/4" 358' w/300 sx. cem.
 5 1/2" 4615' w/150 sx. cem.

Figures Indicate Bottom of Formations.

sand	95
shale	356
red bed and shale	670
shale-streaks of gypsum	1290
shale	1715
lime and shale	1945
shale and lime	3395
lime	3865
lime and shale	4305
viola chert and shale	4392
cherty lime and shale	4445
shale	4503
sand and shale	4545
arbuckle	4614 RTD
lime	4616
Total Depth	

TOPS: SCHLUMBERGER

Heebner	3637
Brown Lime	3812
Lansing	3827
Base Kansas City	4189
Conglomerate	4271
Simpson Sh.	4493
Simpson Sand	4512
Arbuckle	4591

DST: #1-3866, op 1 hr, fair blow, rec. 900'
 gas in drill pipe, 30' SGCM, SI 20 min, IFP 18#,
 FFP 17#, BHP 85#. #2-4008-15, op 1 hr,
 gas to surf 4 min, after 30 min too small
 to measure, rec. 73' gassy OCM & 189' wtr.
 IFP 140#, FFP 155#, BHP 1205#, SI 20 min.
 #3-4020-36, op 1 hr, wk blow, rec. 20'
 mud, SI 20 min, FPs 10#, BHP 120#. #4-4099-4115,
 op 1 hr, gas to surf. 6 min, too little to gauge
 after 40 min, rec. 30' sl GCM, SI 20 min,
 FPs 55#, BHP 1320#. #5-4368-4430, op 45 min,
 gas to surf 3 min (BTU 1058) 45 min ga 1,450,000,
 rec. 60' GCM, SI 20 min, IFP 375#, FFP 425#,
 BHP 1605#. #6-4420-45, op 1 hr, wk blow, rec.
 15' mud, SI 20 min. Pres. 0. #7-4490-5430
 op 16 min, ga 5,020,000 in 15 min, flowed
 mud in 11 min, oil in 15 min, rec. 1054'
 clean oil, 36.6 grav @ 88o. SI 20 min, IFP
 810#, FFP 1278#, BHP 1390#. #8-4592-4614,
 op 1 hr, gas to surf in 30 min, too small
 to measure, rec. 236' muddy gassy oil, SI
 20 min, IBHP 1652#, IFP 48#, FFP 110#,
 FBHP 665#.