

KANSAS DRILLERS LOG

15-151-20408

API No. 15 — 151 — 20,408  
County Number

S. 33 T. 29 R. 13 E  
W  
Loc. C NW SE  
County Pratt

Operator  
Cities Service Company

Address 700 Sutton Pl. Bldg, Wichita, Kansas 67202


Well No. 1 Lease Name Lambert "B"

Footage Location  
1980 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Geologist  
Gabbert & Jones Well Site - John Rose

Spud Date Total Depth P.B.T.D.  
7-21-77 4740 4670

Date Completed Oil Purchaser  
9-6-77 The Permian Corporation



Elev.: Gr. 1890'  
DF 1893' KB 1895'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24#	321	50/50 Poxmix	325	2% CaCl-2
Production	7 7/8"	5 1/2"	15 1/2#	4789	50/50 Poxmix	300	10% Salt 75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
					4608-4612

Size	Setting depth	Packer set at
2"	4664	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 Gallons 15% MCA	4608-4612

INITIAL PRODUCTION

Date of first production 9-6-77 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	85 bbls.	MCF	75 bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s) 4608-4612

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Cities Service Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Lambert "B"	Oil
S <u>33</u> T <u>29</u> R <u>13</u> $\frac{E}{W}$		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
(See Attached Log)				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature
	W. J. Devaney
	Region Operations Manager
	Title
	September 8, 1977
	Date

33-29-13W

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Lambert B-1  
C-1/4-SE Sec 33-29-13W  
Pratt County Kansas

Commenced: 7-21-77

Completed: 8-7-77

OPERATOR: CITIES SERVICE OIL CO.

Depth		Formation	Remarks
From	to		
0	185	Sand	Ran 7 jts of 24# 8 5/8" cag set @ 321' Cemented w/325 sks Common 2% CC 2% Gel PD @ 10:20 a.m. 7-22-77
185	480	Redbed	
480	1172	Sand-Shells	
1172	1720	Shale-Shells	
1720	2075	Shale	Ran 117 jts of 14# 5 1/2" cag set @ 4739' w/40 bbls Salt Flush - 300 sks 50/50 Posmix 10% Salt .75% CFR2 PD @ 5:30 p.m. 8-7-77
2075	2550	Line-Shale	
2550	2980	Line	
2980	3545	Line-Shale	
3545	4740	Line	
	4740 - TD		

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above  
Drillers' Well Log is true and correct to the best of my knowledge and belief and  
according to the records of this office.

GABBERT-JONES, INC.

  
JAMES S. SUTTON II

Subscribed and sworn to before me this 18th day of August, 1977.

  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.