

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

33-29-13W


Company- STRATA DRILLING, INC.
 Farm- Moore No. 1

SEC. 33 T. 29 R. 13W
 C NW NE

Total Depth. 4611'
 Comm. 1-14-63 Comp. 1-26-63
 Shot or Treated.
 Contractor.
 Issued. 4-27-63

County Pratt

KANSAS



Elevation. 1904' RB

Production. Dry

Figures Indicate Bottom of Formations.

clay, sand & shale	201
shale	515
shale & lime	2380
lime	2445
lime & shale	2800
shale w/lime strks.	3015
shale & lime	3930
lime	4390
Chert	4435
lime	4510
lime & chert	4545
Chert	4566
Chert, lime & shale	4607
sand	4611 RTD
Total Depth	

TOPS: SAMPLE

Heebner	3737
Brown Lime	3916
Lansing	3933
Base Kansas City	4324
Mississippi	4393
Viola	4474
Simpson Shale	4595

DST #1 4396-4416' tool op 1 hr. gas
 to surface in 7 min., to small to measure.
 rec. 30' gas cut mud. IBHP 1490 lbs.
 in 20 min. IFP 0#, FFP 0#, FBHP 750#/
 20 min.

DST #2 4474-4510' tool op 1 hr., gas
 to surface in 15 min., to small to
 measure. rec. 75' heavily oil cut mud,
 85' muddy oil. IBHP 1428#/20 min. IFP
 110#, FFP 160#, FBHP 815#/20 min.

DST #3 4515-4545' tool op 1 hr. weak
 blow 35 min. rec. 18' slight oil cut
 mud. IBHP 265#/20 min. IFP 0#, FFP
 0#, FBHP 0#/20 min.

DST #4 4593-4607' tool op 1 hr.
 Flushed tool, weak blow 5 min. rec. 10'
 mud with oil specks. No pressures.