

10-29-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- JONES-GEBERT OIL, INC.  
Farm- Mueller No. 1

SEC. 10 T. 29 R. 21W  
C NW NW

Total Depth. 5280'  
Comm. 2-19-64 Comp. 3-9-64  
Shot or Treated.  
Contractor. Jones-Gebert Oil, Inc.  
Issued. 5-2-64

County Ford  
KANSAS



Elevation. 2413' KB

CASING:

8 5/8" 575' cem w/ 500 sx

Production. DRY

Figures Indicate Bottom of Formations.

soil & shale	100
sand	155
sand streaks & shale	500
sand	520
shale & sand	985
shale	1010
shale & shells	1355
anhydrite	1395
shale & shells	2240
shale w/ lime streaks	2465
lime w/shale	2625
lime	2885
lime w/shale	2970
shale w/lime streaks	3025
lime & shale	3500
sandy lime w/shale	3645
lime & shale	3790
lime w/shale	3930
lime & shale	4115
lime w/shale	4242
lime & shale	4375
lime w/shale	4475
lime & shale	4562
lime	4650
lime & shale	4717
lime	4741
lime w/shale	4808
lime & shale	5014
lime	5088
lime & shale	5105
conglomerate	5135
lime	5280 RTD
Total Depth	

TOPS: SCOUT	
Heebner	4270
Brown lime	4437
Lansing	4446

Base Kansas City	4876
Marmaton	4898
Cherokee	5048
Mississippi	5135