



**SIDE TWO**

Operator Name Pickrell Drilling Company, Inc. Lease Name Cannon Well # 1-A

Sec. 36 Twp. 29S Rge. 25  East  West County Ford

**WELL LOG**

**INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.**

Drill Stem Tests Taken  Yes  No  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No

**Formation Description**  
 Log  Sample

DST #1 5045-5100, 30"-45"-30"-30", wk blow, Rec. 130' drlg mud (NS), IFP 48#-77#, FFP 97#-126#, ISIP 1575#, FSIP 1479#.

DST #2 5240-5285, 30"-30"-30"-30", wk blow died, rec. 15' mud, IFP 39#-39#, FFP 39#-48#, ISIP 39#, FSIP 48#.

DST #3 5299-5350, 30"-30"-30"-30", Rec. 10' mud, IFP 39#-39#, FFP 39#-39#, ISIP 48#, FSIP 48#.

Name	Top	Bottom
Heebner	4364	(-1782)
Lansing	4517	(-1935)
Stark	4870	(-2288)
Base Kansas City	4987	(-2405)
Base Pawnee	5131	(-2549)
Cherokee	5163	(-2581)
Base Inola	5237	(-2655)
Mississippi	5265	(-2683)
LTD	5430'	

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	23#	513' KB	60/40 poz	285	2%gel 3%CC
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record			
Shots Per Foot	Specify Footage of Each Interval Perforated			(Amount and Kind of Material Used)		Depth	
TUBING RECORD				Liner Run	<input type="checkbox"/> Yes <input type="checkbox"/> No		
	Size	Set At	Packer at				
Date of First Production		Producing Method					
		<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (explain).....					