


90054

1-322W
MAP NO. K-83 3030 GR ELEV. 3035DF 3037KB
STATE Kans COUNTY Grant SEC. 25 TWP. 29S RGE. 35W
OPERATOR United Prod. Co., Inc. LOC. C SE NW
WELL NO. 1 FARM NAME S. A. Davis Unit FT. FROM _____ LINE _____
WC FT. FROM _____ LINE _____
FR. 12/1/61 SPUD 12/5/61 COMP. 1/30/62

CONT./GEOL. Garvey Drlg Tools.
COMPLETION RECORD
NAME PRODUCING INTERVAL FROM — TO PERF. W/HOLES TREATMENT RECORD
a CG 2881-3013 160 1250 A
b _____
c _____
d 12 Hr BD Ga:
a I. P. OIL/DIST. 0 WTR. 5 Gal WPH GAS 1210 M.C.F.P.D. _____ CHK. _____ HRS. 24
b " " " " " "
c " " " " " "
d _____



D & A ()
SIP# 425# FI TP # _____ FI CP# _____ SIBHP _____
GOR. _____ GR. _____ PBTD 3167 TD 5712
CASING - CEMENT RECORD
SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8 5/8" 1872 750
4 1/2" 3100 400

OPERATOR United Prod. Co. WELL NO. 1 S.A. Davis Unit ELEV. 3037 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums					
No Sample Tops			Winf	2611	+ 426
			CG	2845	+ 192
			Waub	3262	- 225
TD (St Lou) 5712	-2675		Lans "A"	4102	-1065
			KC "A"	4556	-1519
			Marm Pay	4768	-1731
			Morr	5298	-2261
			St Gen	5624	-2587
			St Lou	5700	-2663
			No LTD		

DST #1 (CG) 2887-2963, Op 1 hr, GTS/30", TSTM, R 150'
GCM, IBHP 510#/30", IFP 20#, FFP 102#, FBHP 489#/30"
DST #2 (CG) 2994-3126, Op 67", GTS/4", Ga 486 Mcfgpd, R
525' GCM, IBHP 583#/30", IFP 178#, FFP 296#, FBHP
573#/30".
DST #3 (KC) 4554-73, Op 1 hr, R 100 GC Mdy SW, IBHP
1276#/30", IFP 126#, FFP 462#, FBHP 1250#/30".
RTD 5712. Log.

246
120

WLT #1 (CG) 3176-78 $\frac{1}{2}$, op 1 hr, rec 2400 cc filt wtr,
SIP 740/30:

WLT #2 (CG) 3126-28 $\frac{1}{2}$, op 1 hr, rec 400 cc filt wtr, FBHP
700/60:

WLT #3 (CG) 3095-97 $\frac{1}{2}$, op 1 hr, no rec, no pressures.

WLT #4 (CG) 3040-42 $\frac{1}{2}$, op 45 min, rec 7.1 cfg + 8400 cc filt
wtr, SIP 615/30:

PB 3167 PBTD, 4 $\frac{1}{2}$ " @ 3100 w/400 sx. 62/3034-47 (CG)

A/500 M, rec 1d, 12 hr BD g 296 MCF + 1 $\frac{1}{2}$ BWPH, Sq

3034-47/75 sx. 68/2996-3013, 24/2973-79, 68/2881-98 (CG),

A/1250, 12 hr BD g 1210 MCF + 5 GWPH, SIP 425# fr CG 2881-3013.

LIBERAL ELECTRIC LOG TOPS

3037 KB

Winfield 2611 (+426)

Council Grove 2870 (+167) g 1,210 MCF + 5 GWPH ϕ

Heebner 4000 (-963)

Toronto 4021 (-984)

Lansing 4102 (-1065)

"D" Zone 4556 (-1518) tst GCXW

Marmaton 4730 (-1693)

Morrow 5306 (-2269)

*"S-3" 5486 (-2449) 6/12, NT

Chester 5528 (-2491)

*Sand 5590 (-2553) 16/16, NT

Ste. Gen 5642 (-2605)

TD 5710

*Operator did not call any sands.

