

FORMATION

TOPS

30

Sec.

29

Twp.

36W

Rge.

NW NW SE

Location

Grant

County

Kansas

State

3064

Elevation

Sinclair Prairie

Company

1

Well No.

Jarvis Unit

Farm

Line

Feet from

Line

Feet from

CASING

8 5/8" 681 ()

5 1/2" 2763 ()

Producing Formation

T. D.

2770

I. P.

14.400M

Date

Sp. 4-5-48.

R.T.D. 2770. RUST C.O. Perf. 263 holes 2671-2719.

A/10,000 gals. Plug @ 2650. Perf. 232 Holes

2604-48. A/5000 gals. Plug @ 2580. Perf. 179 holes

2548-78. A/5000 gals. Drove all plugs to T.D.,

3.302M. Plug @ 2539. Perf. 156 holes 2475-2505.

Perf. 24 holes 2462-67. A/10,000 gals. Perf. 135

holes 2510-34. A/4000 gals., 867MCF. A/5000 gals.,

1.500M. Plug @ 2430. Perf. 127 holes 2396-2420.

A/5000 gals. All plugs to T.D., 7.000M.

A/10,000 gals. all Perfs. 22 hr. S.I., 20 min.

B.D. 12.500M. I.P. 14.400M Del. 1.753M

R.P. 415#

AUG 17 48

GEOL. 90 10M