

State Kansas Field Nichols
 County Kiowa
 Company Gulf Oil
 Farm J. Unruh Well No. 1
 Sec. 30 Twp. Blk. 29S Range Survey 18W
 fr N fr E fr S fr W
 of SE SE NW

Contractor Falcon Seaboard

Remarks
 Comm. 7-19-55 Comp. 8-31-55
 Elev. 2255 T. D. 5022 P. B.
 Pay 4932-40, 4945-58 Guty 3/2°

I. P. 1,120mg w/35 BOPD R. P.
 Casing Record: 13 3/8 7
 20 10 3/4 5/2 5022/100
 16 8 5/8 354/235

Date	Log Description	Notes
7-20-55	TTD 365, ran 8 5/8 @ 354/235, WOC.	Tops <u>Hb 4129</u>
JUL 27 1955	Ø 3880	<u>Drug 4175</u>
AUG 3 1955	Ø 4870	<u>Bye ln. 4344</u>
AUG 10 1955	DST #1 4939-56 up 1/4	<u>Lang-KC 4349</u>
	gts in 3mm	<u>Miss 4929</u>
	g-218 mg an 10 mm	<u>schl'</u>
	rec 120' gem, FP 52-52	<u>Hb 4120</u>
	BN 1540/30	<u>Drug 4174</u>
		<u>Bye ln. 4343</u>
		<u>Lang KC 4346</u>
	Ø #1 4956-63 rec 7' g chert	<u>Miss 4928</u>
	frag, wt. sli foss & frag. rare	
	bleeding of gas & oil	
	Ø #2 4964-72 rec 8'	
	2' chert as above	
	1' chert w/ lime pebbles, no str, below	
	5' ls. gm-out, med x ln, sli foss.	
	RTD 5022 run schl. 4 1/2" e	
	<u>5022/100</u>	

co 54991 try to 4875 - w/p 32 4932-40
52/4945-58 swab 2760 ^{load} in 1 1/2 hrs.
swabbing

AUG 17 1955

did not see load

A/500 mud price/7500 sd/10,000

kicked off & g- 1,200 mg w/6 b load ph.
FCP 475# FTP 350#

planned 80 B load in 24 hrs.

g- 800 mg.

planned 49 BO in 24 hrs.

g- 800 mg FCP 390# FTP 208#

Bureau Mines Bush Pressure Test

planned 48 BO in 23 hrs. then

3 1/2" ck.

g- 619 mg

FCP 590 FTP 420

36.2° Gvty

SIP 1360#

to retreat ~~swab~~

AUG 24 1955

price/15,000 sd/22,500

swab 3760 north in 1 hr.

swab 211 BO in 21 hrs.

5.2 BOPH last 4 hrs. then 2 1/2" kg
g- 6475 mg

CP 390# TP 130#

AUG 31 1955

planned 58 BO in 24 hrs.

FCP 350# FTP 150#

g- 1,100 mg

for planned 35 BO in 24 hrs then 2 1/2" kg
g- 1,120 mg FCP 280# FTP 125#

Gvty 36.2°