

FORMATION

TOPS

31

Sec.

29

Twp.

36W

Rge.

NW NW SE

Location

Grant

County

Kansas

State

3075

Elevation

Sinclair Prairie

Company

Her. 2406

Kri. 2512

Winf. 2552

U.F.R. 2622

L.F.R. 2676

F.Flint 2734

1

Well No.

Limper-Jarvis

Farm

330

Feet from

N Line

of SE/4

330


Feet from

W Line

CASING

8 5/8" 694 ()

5 1/2" 2765 ()



Producing Formation

T. D.

2770

I. P.

23.350M

Date

Sp. 4-16-48.

R.T.D. 2770. RUST C.O. to 2737. Perf. 234 holes

2676-2724. A/15,000 gals. Set plug @ 2662.

Perf. 210 holes 2622-57. A/5000 gals., Set plug

@ 2590. Perf. 209 holes 2552-87. A/6000 gals.

Set plug @ 2540. Perf. 138 holes 2512-36.

A/5000 gals. Set plug @ 2510. Perf. 132 holes

2486-2508. A/2000 gals. Drove all plugs to T.D.

A/10,000 gals. all Perfs. I.P. 23.350M R.P. 405#

φ

JUN 22 48