

90078

6-51W

MAP NO. 83

34-29S-37W

STATE Kans COUNTY Grant

SEC. C NE NE

OPER Hugoton Prod Co. - Garden City, Kansas

FT/FR _____ LINE _____

WELL 2-34 FARM Johnson

FT/FR _____ LINE _____

Geo WC in Hugoton Field * ELEV. 3080 GR. 3087 DF. 3090 KB

CONT. Helmerich & Payne GEOL. _____

CO. INT. 6000' Oil & Gas Test

F.R. 4-18-63 SPUD 4-21-63 COMP. 6-4-63

TD 5880 FM. St Lou PBTD. _____

										*

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		CG	2756-2851		136

1.P. Ga 5,737,000 Cfgpd - SIP 343.2#
*-7 miles N of Morr Gas in Perrill Field
8 5/8" @1761 w/850 sx. 4 1/2" @2983 w/500 sx.

Data Inc.

(KB Log)

Herr	2442	+ 648	Flor Flint	2696	+ 394
U/Kri	2460	+ 630	Wre	2728	+ 362
L/Kri	2484	+ 606	CG	2748	+ 342
Winf	2524	+ 566	Adm	2989	+ 101
U/FR	2578	+ 512	Waub	3170	= 80
L/FR	2638	+ 452	Shaw	3536	- 446
(Cont)					

(KB Log Cont)

Hb	3936	- 846	Morr sh	5279	-2189
Tor	3972	- 882	Miss	5576	-2486
Lans	4036	- 946	St Gen	5738	-2648
Marm	4663	-1573	St Lou	5832	-2742
Chero	4811	-1721	LTD	5872	-2782
Atoka	5110	-2020	RTD	5880	-2790

DST #1 (Pkr fail) - RTD 5880 , Ran Log
 WLTL #1 (St Lou) 5834-36 1/2, Op 1 hr, No Rec No Press recorded
 WLTL #2 (Miss) 5674-76 1/2, Op 2 hrs, R 3650 cc SW, ISIP 1730#/40", FSIP 1700#/30", 4 1/2" @2983 w/500 sx., CO 2950, 16/2847-51 (CG), 1000MA, § sli show gas, Frac 10,000 GA (3%) x 10,000# sd, Ga 430,000 Cfgpd + ld, PB 2842, 40/2827-37 (CG), 1000MA, PB 2822, 24/2812-18 (CG), 1000MA, PB 2803, 40/2782-92, 16/2756-60 (CG), 2000MA, CO 2950, Frac 60,000 GW x 75,000 # sd w/rock salt, Rec ld, 72/20 Ga 5,737,000 Cfgpd, SIP 343.2#, CG 2756-2851 COMPLETED (5-27-63)

LIBERAL ELECTRIC LOG TOPS

3090 KB

Winfield 2524 (+566)
 Council Grove 2766 (+344) @ 5,700 MCF
 Heebner 3936 (-846)
 Toronto 3970 (-880)
 Lansing 4052 (-962)
 "D" 4532 (-1442)
 Marmaton 4662 (-1572)
 Pay Zone 4698 (-1608)
 Morrow 5278 (-2188)
 "S-3" Zone 5470 (-2380) ?16/26; NT
 Chester (Shale) 5508 (-2418) WLT XW
 Ste. Gen 5738 (-2648)
 St. Louis 5836 (-2746) WLT no rec
 TD 5880

386 + 858
 848 + 348
 101 + 880
 08 - 010
 344 - 388

(Cont)

278 - 218
 278 - 248
 278 - 248
 278 - 248
 278 - 248
 278 - 248

(Faint, mostly illegible text at the bottom of the page, possibly bleed-through or a second page's content.)