

Pl.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg., Wichita, Kansas.

COLUMBIAN FUEL CORP.
A.G. English 1 "A"

SEC. 2 T. 29S R. 36W
Center SW $\frac{1}{4}$

Total Depth. 2870'
Comm. 3-19-36 Comp. 4-28-36
Shot or Treated.
Contractor.
Issued. 5-23-36

County, Grant



Elevation. 3038

CASING.

12 $\frac{1}{2}$ " 500' left in
8 $\frac{1}{4}$ " 2303' left in

Production. 7 M. Gas.
R.P.: 410# in one hour.

Figures Indicate Bottom of Formations.	
surface clay	48
sand	200
clay	256
sand hard	510
shale & sand	675
red bed	925
red bed & anhydrite	1256
red bed & gyp	1330
sand & streaks of	
red bed	1540
sand & red bed	1715
red bed & gyp	2210
anhydrite	2303
lime	2330
broken lime & slate	2440
red rock	2447
lime hard	2461
brown & blue shale	2466
broken lime & dolomite	2486
dolomite	2500
slate	2513
dolomite S/G	2527
broken lime	2561
lime	2565
slate	2570
lime	2580
shale red	2582
dolomite	2608
lime broken	2623
shale red	2642
dolomite	2675
sandy lime	2770
red rock & lime	2789
sandy lime	2870
Total Depth	

REMARKS: Gas 2530-2552'
Gas 2687-2715'

Well was shot from 2530-2552 with 60 quarts of
Solidified and from 2687-2715 with 240 quarts.