


COLUMBIAN FUEL CORP.
H.V. Maxwell No. 1.

SEC. 4 T. ²⁹~~26~~ R. 36 W
Cen SW ¹/₄

Total Depth. 2724'
Comm. 6-4-37 Comp. 7-9-37
Shot or Treated. 40 Qts 2690-2700 &
Contractor. 40 Qts. 2636-45
Issued. 7-24-37

County. Grant



Elevation.

CASING:
12 ¹/₂" 552'
8 ¹/₂" 2462'
6 5/8" 272'

Production. 6,500,000 Gas

Figures Indicate Bottom of Formations.

surface sand	25
sand white hrd	60
sand & clay	300
sand & gravel	390
shale	425
sand hrd	460
shale	510
shale & sand	650
shale & gyp rock	690
shale	765
red bed & shale	910
shale	1045
red bed & shells	1150
gyp & red bed	1280
shale & shells	1600
red bed & shells	1815
gypsum	1875
red bed & shells	2014
shale & gypsum	2190
anhydrite	2245
shale red & blue & anhydrite	2329
anhydrite & shale	2430
anhydrite hrd	2473
shale brown & blue	2481
lime grey	2486
lime	2513
sh gas 2494-2513	
shale blk	2515
lime flinty hrd & blk	2519
lime hrd	2546
shale chocolate	2558
shale & lime shells	2568
shale grey lgt	2575
sdv grey shale	2595
shale red	2628
shale grey sdv	2636
sdv lime inc in gas	2654
shale blue	2685
sdv limo	2700
Inc in gas 2685-2700	
shale blue	2703
sdv lime	2710
cherty lime	2724
Total Depth.	

6 5/8" csg 272' perforated from 2494-2513 and
from 2638-2644 and from
2685-2700. Balance of liner
blank with shoe on bottom
and J. Tool shoe on top.