


COLUMBIAN FUEL CORP.
Addie Bass No. 1.

SEC. 7 T. 29 R. 36W
Cen SE

Total Depth. 2723'
Comm. 8-28-37 Comp. 9-25-37
Shot or Treated.
Contractor.
Issued. 11-6-37

County. Grant



CASING:
12" 523'
8" 2438'
6" 262' (Liner)

Elevation.

Production. 11,500,000 G.

Figures Indicate Bottom of Formations.

surface	35
sand	140
sand & clay	275
sand hrd, gravel & clay	355
sand & clay	420
sand hrd & gyp	475
shale, shells & clay	523
shale & shells	680
red bed & shells	1010
shale & shells	1170
gyp & shale	1280
shale & shells	1965
anhydrite & shale	2327
anhydrite	2443
dolomite	2445
slate brown	2453
lime grey hrd	2468
dolomite	2476
lime grey hrd	2490
lime grey	2504
lime shells	2510
dolomite	2521
shale red	2532
lime grey	2548
lime blue	2567
shale red	2595
lime grey hrd	2602
shale green & little	
brown shale	2610
lime grey hrd	2628
lime blue	2640
shale grey & lime	
shells	2646
lime blue sdy	2679
lime grey	2697
brkn lime & shale	2710
lime hrd	2715
shale red & shells	2723
Total Depth.	

Gas Pays

2485-2518
2538-2562
2615-2632
2648-2672

Shot:

80/2648-72
60/2615-2632
75/2538-2562
80/2485-2514