

19-29-37W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HUGOTON PROD. CO.
Farm- Winger No. 1

SEC. 19 T. 29 R. 37N
SW SW SW NE
2440' S. of N.L. & 2380' W. of
E.L.

County Grant

KANSAS



Total Depth. 2651
Comm. 6-2-51 Comp. 6-23-51
Shot or Treated.
Contractor. Moran Bros., Inc.
Issued. 10-6-51

CASING:

10 3/4" 538' cem. w/325 sx circ.
7" 2395' cem. w/800 sx circ.
5 1/2" 280' slotted liner

Elevation. 3097 Gr.
3120 (sand)

Production. 19,794,000 gas

Figures Indicate Bottom of Formations.

surface	75
clay & sand	520
red bed	555
red bed	925
shale & gypsum	2360
anhydrite & lime	2410 RTD
lime	2488
odell shale	2498
lime	2541
gage shale	2545
gage shale	2561
Ft. Riley lime	2651
Total Depth	

Tops:	
Hollenberg	2375
Herington	2405
Krider	2428
Winfield	2497
Upper Ft. Riley	2560
Lower Ft. Riley	2600

GAS LOG:

Gas Log	M.C.F.
2450	FS/G
2480	2019.6
2488	2019.6
2520	2226.6
2525	2535.8
2527	3211.0
2534	3075.8
2541	3075.8
2569	3139.2
2574	3109.6
2587	3109.6
2602	3757.2
2613	3559.7
2620	3473.0
2638	3346.2
2651	3311.7