

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

12-29-37W

Company- HUGOTON PRODUCTION COMPANY
Farm- Carter No. 1

SEC. 12 T. 29 R. 37W
CSW

1320' N. of SL & 1320' E. of
WL, SW $\frac{1}{4}$
County Grant

KANSAS

Total Depth. 2612


Comm. 8-29-52

Comp. 9-12-52

Shot or Treated.

Contractor. Moran Bros. Inc.

Issued. 11-15-52



CASING:

10 3/4" 560' cem. w/325 sx circ.
7 5/8" 2388' cem. w/800 sx circ.

Elevation. 3006 (m)
~~3042.77~~
3007 (sand)

Production. 34,600,000 Gas

Figures Indicate Bottom of Formations.

surface	15
sand, gravel & clay	375
shale & sand	540
red bed	570
red bed	760
red bed & gyp	1040
shale & gyp	2365
lime	2400 RTD
lime	2450
Odel shale	2460
lime	2499
gage shale	2520
Ft. Riley lime	2602
lime	2612
Total Depth	

Tops:	
Hollenberg	2328
Herington	2377
Krider	2392-2452
Winfield	2460-2500
Upper Ft. Riley	2520-2566
Lower Ft. Riley	2570

Gas Log:	M.C.F.
2409	F.S.G.
2450 (after acid)	2699.8
2504	3346.2
2550	3346.2
2566	3587.4
2575	3532.1
2591	3696.9
2602	3532.1
2612	3277.3