

AUG 28 1972

16-29S-38W

## KANSAS DRILLERS LOG

API No. 15 — 067 — 20,221  
County Number

Operator

Amoco Production Company

Address

P. O. Box 432 - Liberal, Kansas 67901

Well No.

2

Lease Name

Redinger Gas Unit "A"

Footage Location

1250 feet from (S) line 2590 feet from (W) line

Principal Contractor

Service Drilling Company

Geologist

Spud Date

8-5-72

Total Depth

2847

P.B.T.D.

2846

Date Completed

8-24-72


Oil Purchaser

S. 16 T. 29 S. R. 38 W

Loc. 1250' FSL X 2590' FWL

County

Grant

640 Acres  
N

Elev.: Gr. 3119

DF KB

## CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	23	730	Class "A"	385	3% CACL
Production	7-7/8	5-1/2	14	2847	Special	530	18% CACL

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2	2693-97, 2736-56
					2774-79, 2798-2801
					2814-16, 2823-34

## TUBING RECORD

Size	Setting depth	Packer set at

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Speckhead w/2500 Gal. 15% Acid. Frac w/100,000 Gal water and 100,000# Sand	2693 - 2834


## INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
8-24-72		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	6,700	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Waiting on pipeline connection			2693 - 2834		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Amoco Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: <div style="text-align: right;">Gas</div>	
Well No. 2	Lease Name Redinger Gas Unit "A"		
S 16 T 29 N R 38 E W			
<b>WELL LOG</b>		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Sand - Red Bed	0	650	
Red Bed	650	731	
Sand - Anhydrite	731	1798	
Sand - Shale	1798	2080	
Shale - Lime	2080	2260	
Lime - Shale	2260	2472	
Shale - Lime	2472	2720	
Lime - Shale	2720	2847	
Test Info: 24 Hr. SIP <u>248</u> # 20 Min. Open Flw <u>6.7</u> MMCFD.			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Signature  
 J. W. VAUGHN  
 Area Administrative Supervisor  
 Title  
August 25, 1972  
 Date