

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - STANOLIND OIL & GAS COMPANY
Farm - Lawrence Gas Unit No. 1

SEC. 3 T. 29 R. 38W
Cen. Sec.

Total Depth. 2588'
Comm. 11-18-46 Comp. 12-3-46
Shot or Treated.
Contractor.
Issued. 2-1-47

County. Grant

KANSAS



Elevation. 3111 feet

CASING:

8-5/8" 647' Cem w/275 sx
5-1/2" 2557' Cem w/350 sx

Production. 7,750,000 Gas
20 min. open flow test

Figures Indicate Bottom of Formations.

clay & sand	455
sand	550
red bed	650
red bed & sand	821
red bed, gyp shells & sand	1099
anhydrite	1137
red bed & brkn shale	1408
brkn shale & sdy shale	1723
lime sdy shale	1901
brkn lime & shale	2030
sand, lime & shell shale	2154
lime & shale	2325
lime	2400
lime & shells	2523
lime & shale	2534
brkn lime & shale (Cable)	2580
lime	2588
Total Depth	

Tops:	
Herrington	2372-2392
Krider	2394-2414
Winfield	2434-2468
Towanda	2506-2530
Ft. Riley	2555-2581

Rotary Tools were used from 0'
to 2530'.
Cable Tools were used from 2580'
to completion.