


WELL LOG BUREAU · KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm - Shore Gas Unit "B" No. 1

SEC. 22 T. 29 R. 39W
SW SW NE
2790' NSL, 2790' EWL of NE/4

Total Depth. 2540
Comm. 10-29-49 Comp. 12-2-49
Shot or Treated.
Contractor.
Issued. 1-7-50

County. Stanton
KANSAS



CASING:
10 3/4" 608' ccm w/350 sx.
7" 2498' ccm w/700 sx.

Elevation. 2180 Ind.

Production. 6,373,000 gas

Figures Indicate Bottom of Formations.

clay	344
shale, sand	570
red bed	608
shale	790
shale, anhydrite	1255
salt, shale, anhydrite	1657
shale	2080
lime, shale	2295
lime	2360
lime, dolomite	2540
Total Depth	

Tops:
Herington-Krider 2309-2358
Winfield 2376-2410
Towanda 2437-2473
Ft. Riley 2498-2540

Ran Schlumberger to 2540'
Lane Wells Jet perforated w/420 shots.
Acid Engr. Acid w/18,500 gals 15%.