


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm McIver Gas Unit No. 1

SEC. 26 T. 29 R. 39W
SW SW NE
2790' NSL, 2790' EWL of NE/4

Total Depth. 2553
Comm. 10-21-49 Comp. 11-10-49
Shot or Treated.
Contractor.
Issued. 1-7-50

County. Stanton
KANSAS



CASING:
10 3/4" 609' cem w/350 sx.
7" 2502' cem w/900 sx.

Elevation. 3182 Ind.

Production. 13,178,000 gas

Figures Indicate Bottom of Formations.

surface clay	50
sand, gyp	570
red bed	609
redbed, anhydrite	810
red bed, sand	1200
anhydrite, sand, shale	1442
shale, sand	1696
shale, anhydrite	1865
lime	2055
lime, shale	2165
lime	2292
lime, dolomite	2381
lime	2553
Total Depth	

Tops:
Herington-Krider 2314-2368
Winfield 2386-2422
Towanda 2449-2481
Ft. Riley 2502-2545

Schlumberger ran to 2553'.
Lane Wells jet perforated w/4 SPF
as follows:

Herington-Krider, 2314-2368
Winfield, 2386-2422
Towanda, 2449-2481.

Acidization:
Ft. Riley, 1000 gals 15%.
Herington-Krider 1000 gals 15%.
Winfield 1000 gals 15%.
Towanda 1000 gals 15%.
All zones w/33000 gals 7½%.