

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm - Full Gas Unit No. 1

SEC. 27 T. 29 R. 39W
SW SW NE
2490' SN1 & 2490' WEL NE/C

Total Depth. 2535'

Comm. 5-8-48

Comp. 6-7-48

Shot or Treated. Acidized

Contractor.


Rotary Tools 0' to 2337'

Issued. 8-7-48

Cable Tools 2337' to 2535'

County. Stanton

KANSAS



Elevation. 3200 feet

CASING:

10-3/4" 590' Cem. W/300 Sx.

7" 2314' Cem. W/350 Sx.

Production. 20 min. open flow
6,115,000 Gas. S.I.P. 440#.

Figures Indicate Bottom of Formations.

sand & shale	550
red bed	910
sand & shale	1200
shale	1300
salt	1475
shale & lime	1674
shale & anhydrite	1755
anhydrite	1875
anhy. & shale	1999
shale & lime	2120
lime	2350
red bed	2380
lime	2395
shale blue	2400
shale gy	2425
red bed	2450
shale gy	2470
red rock	2495
red rock	2535
Total Depth	

Schlumberger Ran To 2535

Acidization:

All zones AW 2000 gals. 15%

Displaced. Max press 350#.

Broke to vac. Time 16 mins.

REAW 14,000 gals. 15%. 11,130

gals flush. Max prsss. 125#.

Broke to vac. Time on acid

10½ mins., on flush 9½ mins.

Tops:

Herington-Krider 2313-2345

Winfield 2376-2408

Towanda 2441-2468

Ft. Riley 2494-2535