

pc

14-29-4W

DRILLER'S LOG

State Geological Survey
Geological Survey

BERRY PETROLEUM CORPORATION
 Woolf No. 1-14
 2310'FNL & 2310' FEL
 Sec. 14-29S-4W
 Sedgwick Co., Ks.

Commenced: 4-11-81
 Completed: 4-19-81

Surface Casing: 203' of 8-5/8"
 cemented w/175 sx common, 3% cc,

FORMATION

DEPTH

Surface Hole	0 - 205
Sand & Shale	205 - 490
Shale & Sand	490 - 956
Lime & Shale	956 - 1517
Shale	1517 - 1803
Shale & Lime	1803 - 2900
Sand & Shale	2900 - 3036
Lime & Shale	3036 - 3237
Shale & Lime	3237 - 3513
Lime & Shale	3513 - 3840
Lime	3840 - 3856
Lime & Shale	3856 - 4289
Sand	4289 - 4302
Shale & Lime	4302 - 4342
Lime	4342 - 4410 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson, Jr.
 James L. Donelson, Jr.

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 24th day of April, 1981

Dorothy L. Schmidt
 Dorothy L. Schmidt, Notary Public



DST (1) 4273-4302(SIMP)/30-60-60-120
201M W/ RBSO, SIP 1330-1295#, FP
20-10/30-10#, HP 2050-2005#
D&A - NO OTHER INFO TO BE RELEASED
AT PRESENT - WILL RELEASE INFO WHEN
AVAILABLE



**BERRY
PETROLEUM
CORPORATION**

State Geological Survey
WICHITA, BRANCH

SUITE 950 • CITY NATIONAL BANK TOWER • OKLAHOMA CITY, OKLAHOMA • 405-236-3606 • 73102 USA

April 20, 1982

Tops for Berry Petroleum Corporation #1-14 Woolf
Section 14-T29S-R4W
Sedgwick County, KS.

KB = 1338'

Heebner	2616 - 1278
Stalnaker	2904 - 1566
Kansas City	3211 - 1873
Marmaton	3492 - 2154
Cherokee	3668 - 2330
Mississippian	3838 - 2500
Kinderhook	4168 - 2830
Simpson	4273 - 2935
Arbuckle	4361 - 3023

No other tests besides DST #1. D & A

cc: Kansas Geological Survey
4150 Monroe
Wichita, Kansas 67209

State Corporation Commission
Conservation Division
200 Colorado Derby Building
Wichita, Kansas 67202