

33-29-4W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- The TEXAS CO.
Farm- Mary Casner No. 1

SEC. 33 T. 29 R. 4W
NW NE NE

Total Depth. 4383
Comm. 4-17-54 Comp. 5-5-54
Shot or Treated.
Contractor. Stickle Drlg Co.
Issued. 5-29-54

County Sedgwick
KANSAS



CASING:

10 3/4" 511' cem w. 525 sx.

Elevation. 1380 D.F.

Production. Dry

Figures indicate Bottom of Formations.

red bed 5- 205
red bed, shale, shells 511
red bed, sand 645
shale salt, shells 890
anhydrite 923
shale, lime 1230
lime, shale 1805
shale 1962
shale, lime 2360
lime 2468
lime, shale 2672
lime brkn 2744
lime chalky, shale 2835
lime, shale 2915
sand, shale 3040
sand 3155
sand, shale 3255
shale, lime 3340
lime, shale 3405
lime 3553
lime, shale 3913
shale shells 3935
chat, lime 3957
lime 4050
lime brkn & cherty 4135
lime 4233
lime, shale 4368
sand 4383
Total Depth

Tops:
Severy Sand 2305
Topeka 2353
Heebner 2730
Stalnaker 3070
Lansing 3145
Kansas City 3310

Basic Kansas City 3523
Marmaton 3602
Cherokee 3738
Miss. 3935
Kinderhook 4260
Chattanooga 4339
Simpson 4356

RTD 4383

