

27-29-7W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DRILLERS PRODUCTION CO., INC.
Farm- Voran "B" No. 2-W

SEC. 27 T. 29 R. 7W
SW SW SE
110' W & 140' S of C SW SE

Total Depth. 4836'
Comm. 8-1-61 Comp. 8-17-61
Shot or Treated.
Contractor. Gabbert-Jones Drlg. Co.
Issued. 11-4-61

County Kingman
KANSAS



Elevation. 1515' KB

Production. SWDW

CASING:

8 5/8" 265' cem w/200 sx.
5 1/2" 4670' cem w/200 sx.

Figures Indicate Bottom of Formations.

red bed & shale	265
red bed & shale	1000
Anhydrite & lime	1325
shale & lime	1500
lime	1705
shale & lime	3198
sand	3302
lime & shale	3350
lime	3828
shale & lime	4110
lime	4389
shale	4495
lime & shale	4505
sand	4575
shale & lime	4615
lime	4836
Total Depth	

TOPS:

Lansing	3310
Base Kansas City	3820
Mississippian	4110
Kinderhook	4387
Simpson	4506
Arbuckle	4626