

28-29-9W
C NE SE

MAY 1 1971

7,000,000 CF6PD
Topeka

GORTZ #1

REX & MORRIS, ETAL

ELEVATION: 1664 RB
1659 GL

TOTAL DEPTH: 4545' RB
CONTRACTOR: RED TIGER DRILLING CO.
COMMENCED: 2-12-1970
COMPLETED: 3-9-1970
INITIAL PROD.: 5000 MCFFD

LOCATION: CENTER NE SE
SECTION 28-29S-9W
KINGMAN COUNTY, KANSAS

CASING RECORD:
8 5/8" OD SET AT 275' W/250 SACKS
4 1/2" OD SET AT 3072' W/100 SACKS

FORMATION

DEPTH

RED BED & SHELLS
RED BED
SHALE
SHALE & SHELLS
LIME & SHALE
SANDY LIME
TOPEKA LIME
SANDY LIME
SHALE & LIME
LIME RTD

280'
550'
990'
1450'
2855'
2926'
2943'
2955'
4250'
4545'

Log Log
Winfield 1656
Indian Cane 2394
Wabash 2420
Tarkenton 2471
White Cloud 2765
B. " 2800
Howard 2822
Topeka 2924
Hebner 3352
Lansing 3572
B.K.C. 4022
misch 4238
Kindershook 4372
Viola 4530

RIGGED UP DERRICK PULLING UNIT. RAN GAMMA RAY-SONIC LOG. PERFORATED 2927'-2929' & 2932'-2936' WITH 4 JET SHOTS PER FOOT. ACIDIZED WITH 500 GALLONS REGULAR MUD ACID.

WORKOVER - 12-8-70 TO 12-10-70

RIGGED UP DERRICK UNIT & KILLED WELL. RAN GAMMA RAY & COLLAR LOG. PERFORATED 2828'-2830' & 2837'-2839', 4 JET SHOTS PER FOOT & SET BAKER BRIDGE PLUG AT 2860'. RAN TUBING & ACIDIZED WITH 250 GALLONS OF MUD ACID & TESTED. ACIDIZED WITH 2000 GALLONS 15% REGULAR ACID.

I HEREBY CERTIFY THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REX & MORRIS DRILLING COMPANY

BY A.H. Fisher
A H FISHER