

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-2-18w

Company - HONAKER DRILLING CO., INC. ET AL
Farm - Fogleman No. 1

SEC. 4 T. 2 R. 18W
NW NW SE

Total Depth. 3555
Comm. 8-2-50 Comp. 8-10-50
Shot or Treated.
Contractor.
Issued. 9-9-50

County. Phillips
KANSAS



CASING:
8 5/8" 250' cem w/125 sx.

Elevation. 2231 RB

2229 Ind

Production. Dry

Figures Indicate Bottom of Formations.

top soil, clay	50
sand, clay	110
sand	210
sand, shale	550
shale, shells	700
sand, shale	940
broken lime	1000
sand, shale	1170
sand	1325
shale, shells	1825
anhydrite	1865
shale, red bed	1935
red bed	2010
shale, shells	2375
lime, shale	3405
lime	3555

Total Depth (R.B. measurement
less 4' to ground level,
3551')

Tops:

Cimarron Anhydrite	1825	(driller)
Heebner Black Shale	3406	
Lansing -KC Lime	3432	

Remarks: 3450-56 Partly oolitic and fossiliferous lime-spotted, slight porosity-water with very spotted oil staining.
3523-26 Partly crystalline and vugular lime-very spotted slight porosity-trace of stain.
3540-43 Trace slightly porous (pinpoint) lime-spotted, slight stain.
No commercial shows of oil were encountered.
Well plugged and abandoned.

(Measurements are from top of rotary bushing.)