

7-2-186

Company- B &amp; R DRILLING CO.

Farm- Reece "C"

No. 7


SEC. 7

T. 2

R. 18W

County Phillips

KANSAS



Total Depth. 3485

Comm. 1-9-52

Comp. 1-19-52

Shot or Treated.

Contractor.

Issued. 4-26-52

## CASING:

8 5/8" 186 cem. w/130 sx.

5 1/2" 3484 cem. w/150 sx.

Elevation. 2222

Production. 78 bbls. / no  
wtr.

Figures indicate Bottom of Formations.

|                        |        |
|------------------------|--------|
| surface clay           | 95     |
| sand                   | 155    |
| shale                  | 420    |
| shale, sand            | 600    |
| shale, shells          | 1010   |
| shale, sand            | 1095   |
| shale                  | 1160   |
| sand                   | 1210   |
| sand hrd, pyrite       | 1250 ✓ |
| shale, shells, sand    | 1270   |
| shale, sand            | 1510   |
| red bed, shale, shells | 1800   |
| shale, shells          | 2030   |
| shale, lime            | 3060   |
| lime                   | 3218   |
| lime sdy.              | 3250   |
| lime                   | 3455   |
| lime, shale            | 3485   |
| Total Depth            |        |

Tops: Scout

Heebner 3330

Lansing 3357