


CARTER OIL CO.
Friebus No. 1

SEC. 36 T. 2 R. 19W.
CWL SW NW

DISCOVERY WELL

Total Depth. 3861 $\frac{1}{2}$
Comm. 5-29-41 Comp. 6-14-41
Shot or Treated.
Contractor.
Issued 8-16-41

County Phillips



CASING.

103/4" 225' Cemented.
5 1/2" 3475

Elevation

Production Pot. 328 B.

Figures Indicate Bottom of Formations.

clay yellow	65	shale	3391
shale & shells	235	lime	3420
shale	300	shale lime broken	3450
chalk	360	lime broken and	
sand	375	shale	3500
shale	700	lime and shale strks	3528
sand and shale	1005	shale & shells	3539
shale and shells	1070	cored	3556
sand lime shells	1100		
sand and shale	1420	cherty lime	3356
red rock and shale	1460	lime cored	3572
shale	1560	cored	3573
anhydrite	1605	lime and shale	3590
broken lime	1655	lime	3707
lime and shale	1666	lime and sand	3724
sand and shale	1675	sand	3728
red rock and shale	1860	sand and dol.	3790
shale	1935	Basal sand	3802
shale and lime		lime sdy	3815
streaks	2042	Granite wash	3861
sdv shale	2060	Granite	3861 $\frac{1}{2}$
lime	2125		
lime broken	2205	Total Depth.	
lime and shale	2228		
red rock	2234	6-19-41 Running Rippor	3334-37
shale	2242	6-20-41 Ripping Pipe	3337-45
lime	2406	show oil, bailing, testing hole, 1 bbls	
lime rough	2418	acid. Swabbing hole.	
lime	2500		
lime broken & shale	2561	6-21-41. Ripped pipe	3312-19 and 3354-59
chalk	2573	2000 acid. bailing, testing.	
cherty lime	2578	6-22-41 Swabbing, testing, made 5 B.P.I	
sand and lime	2605	6-23-41 Set plug 3325, No Oil	
sdv lime	2620	ripped pipe from	3277-81
lime	2670	ripped pipe from	3256-61
lime broken	2730	6-24-41 Acid 1000 gal. Swabbing testing	
shale	2740	6-25-41 Acid 2000 gal. Swabbing 5' oil in tank	
sdv shale	2763	6-26-41 Swabbing	
shale & shells	2814	6-27-41 Ripped pipe	3240-45
chalk	2824	Swabbing and Testing.	
lime and shale	2830	<u>RIPPED PIPE RECORD.</u>	
lime	2910	3329-44	
shale	2925	3312-19	
shale and lime	2957	3357-59	
lime	3018	3278-82	
sdv lime	3048	3257-60	
(3138.3 equals 3151.3 S.L.M. Corr.)		3240-45	
lime	3156		
lime soft break	3162	TOPS. Anhydrite	1560
lime	3175	Kans. City	3169
lime donso	3230	Arbuckle	3535
chert & lime	3246	Granite wash	3815
shale	3257	Top Granite	3861
lime Odor	3260		
lime	3338		
lime Coring	3346		
coring	3349		
lime	3357		
cored	3374.6		