

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Plotted
Hardy
12-2-1947

Company PHILLIPS PETR.
Farm Argan

No. 4

SEC. 12 T. 2 R. 19W
SE SE SE

Total Depth. 3364'

Comm. 8-27-47


Comp. 11-14-47

Shot or Treated.

Contractor.

Issued. 6-5-48

County. Phillips
KANSAS



Elevation. *2161*

Production. 34 bo & 4 bwpd

CASING:

8" 1838'
5" 3357'

Figures Indicate Bottom of Formations.

surface soil	70
shale	670
sand and shale	970
shale, lime, and shells	1065
sand	1100
lime	1115
shale and shells	1245
sand, lime, and shells	1430
lime	1500
shale	1640
shale, lime, and sand	1791
lime	1851
lime and shale	2010
shale	2093
red bed and shale	2240
lime, shale, and red bed	2350
shale	2925
lime	3160
shale	3190
lime	3364

Total Depth

Heebner 3240

Lansing-Kansas City 3265

3262-68 Slight porosity, no shows

3279-82 & 3283-85; light stain, odor

3313-22 fair porosity, fair stain &
fair odor

3332-36 poor to fair porosity,
spotted saturation, fair odor

SO @ 3355; @ 3364 swb. 55 bo & 14 bw/
21 Hrs.

LWP 3350, perf. 34 S 3331-36, 500 A,
Swb. 21 bo/7 Hrs., 40 S 3313-21,
Swb. 13 bo/14 Hrs.

LWP 3302, perf 28 S 3279-86 500 gals,
Swb 3 1/2 boph

Drove plugs to bottom