

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

502 East Murdock,

Wichita, Kansas


12-2-194

Company- PHILLIPS PETROLEUM COMPANY
 Farm- Argan No. 6

SEC. 12 T. 2 R. 19W
 CE/2 NE SE

Total Depth. 3502 PB 3457
 Comm. 11-9-51 Comp. 12-20-51
 Shot or Treated.
 Contractor.
 Issued. 2-9-52

County Phillips
 KANSAS



CASING:

8" 527' cem w/400 sx.
 5" 3502' cem w/150 sx.

1256(m)
 Elevation. 2156 DF
 2158 (rod)

Production. I.P. 79 No & 153 BW

Figures Indicate Bottom of Formations.

clay	40
sand	70
shale	90
sand	120
shale, shells	425
shale	910
sand	1011
shale	1500
sand	1650
shale, shells	1889
shale	2240
lime, shale	3502
Total depth	
Plugged back to	3457

Tops:
 Heebner 3251
 Toronto 3278
 Lansing-Kansas City 3295
 Base L. K. C. 3495

Note: This test has the
 following zones open by
 perforating:

3340-50; 3418-28; 3382-94;
 3370-78; 3345-52; 3327-36;
 3295-3306; 3278-3284.