

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas


*Plotted
Hardy
13-2-1948*

Company - COOP. REFY. ASSN.
Farm - Dusin No. 4

SEC. 13 T. 2 R. 19W
NE SE NE

Total Depth. 3347'
Comm. 4-9-48 Comp. 4-18-48 ✓
Shot or Treated. Acidized
Contractor.
Issued. 6-26-48

County. Phillips
KANSAS



CASING:
5-1/2" 3316'

Elevation. 2151 Ind.

Production. 55 Bbls.

Figures Indicate Bottom of Formations.

cellar	5
clay & sand	100
shale	720
sand	920
shale, shells, & red beds	1325
shells & redbed	1425
shale & shells	1940
shale	2075
shale & shells	2215
lime brkn	2500
lime & shale	2546
lime	2570
lime brkn	2655
lime & shale	2875
lime brkn	3075
lime RTD	3321
Lansing KC lime	3347
Total Depth	

Tops:
Heehner 3218
Lansing K. C. 3248

Open hole acidized w/
3000 gals. Swabbed 5
Bbls. oil per hr, dropped
to 1 1/4 BOPH. Set Lane-Wells
plug at 3309. Perforated
3307-09 w/3 holes; perforated
3266-75 w/26 holes: acidized
w/6000 gals. Swabbed 125 BO
first 3 hrs. Drilled out
lane-wells plug. Perf. 3295-3304
w/23 holes.