

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


photostat
en
19-2-1946

Company - MAZDA OIL CORP.
Farm - Brands No. 1

SEC. 19 T. 2 R. 19 W
SWc SW

Total Depth. 4121'
Comm. 6-16-44 Comp. 7-2-44
Shot or Treated.
Contractor. Thos. H. Allan
Issued. 7-8-44

County. Phillips
KANSAS



CASING:
8 5/8" 263' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

soil & sand	0-135
chalk yellow & shale	170
shale chalky	263
shale & chalk	600
shale blue	1000
Dakota sand & shale	1600
shale red	1872
anhydrite white	1900
shale red	2380
sand	2420
lime & shale	2870
shale	3154
lime & shale	3248
Topeka lime & shale	3350
Very soft sandy zone	3380
lime & shale	3491
Lansing lime	3500
K.C. lime w/shale	
breaks	3725
Marmaton sand red	3740
shale	3850
dolomite (Arbuckle)	
sft & hrd	4110
Granite wash	4121
Total Depth.	

Tops:

Base Ft. Hays	600
Anhydrite	1872
Topeka	3248
Lansing	3491
Arbuckle	3850
Granite Wash	4110