

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas

*Plotted
Hardy*


ALLAN & COOPERATIVE
Kaiser No. 1

SEC. 25 T. 2 R. 19 W
CSW SW

25-2-1944

Total Depth 3346
Comm. 8-11-42 Comp. 9-13-42
Shot or Treated.
Contractor. Thos. H. Allan.
Issued. 10-10-42

County Phillips



CASING.

85/8" 65' cemented.
6 1/2" 3292' cemented.

Elevation.

Production. Pot. 7 bbls
Per Hr. Swab.

Figures Indicate Bottom of Formations.

Cem. 85/8" surface csg w/30 sacks in			
top of Smokey Hill chalk beds	65	rigging up cable tools.	
chally shale, blue shale, Dakota		shale rod	3294
sandstone group & red beds	1500	buff dense limo, slightly	
red sdy grit	1596	cherty, slight sh oil	3297 ✓
Permian anhydrite	1616		
red shale and red sdy grit	2180	white crytalline limo	3302
porous wh speckled limestone	2200	green and grey shale	3304
(Ft. Riley (Probably wtr)		fossiliferous limestone	3307
shale	2280	shale grey	3310
buff crystalline limo	2300	wh cryst lime-slight sh oil	3316 ✓
shale grey and red	2410	lime-fair sh oil	3318 ✓
crystalline limo white fine	2420	dense white limo	3328
shale	2440	shale	3330
light buff crystalline porous		Treated 500 gal acid	
limo (probabbly wtr)	2460	Swabbed 1 bbl /hour	
shale	2510	shale	3332
lime hard buff	2530	dense buff lime	3335
grey and red shales with few limo		lime porous - fair sh oil	3337 ✓
shells	2870	dense buff limo	3346
white porous limo - fusulinids		Total Depth.	
water	2900		
shale	2975		
fine sand	2990	Treated 1000 gal acid.	
shale red	2998	Swabbed 3 bbls per hr.	
limo grey speckled (Topoka)	3015	Treated 4000 gal acid.	
shale and shells	3045	Swabbed 6 1/2 bbls hr.	
cherty limo white	3055	Perforated 24 shots 3221-28 &	
shale	3070	24 shots 3240-47	
limo	3080	Treated 2000 gal acid over tubing	
very soft dolomitic sandy grit	3115	packer. All pays Swabbed 7 bbl/hr	
shale and shells	3223		
very cherty white crystalline limo			
Lansing? slight show oil	3228 ✓		
hard white crystalline limo	3233		
pyritic shale	3240 ✓		
limo white	3242		
partly oolitic limo with good			
show oil	3246 ✓		
lime dense white	3260		
shale blk	3262		
shale dark grey	3275		
amber chert	3277		
white crystalline limo show oil	3283		
shale red	3292		