

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-2-24W

Company- RAYMOND OIL CO. & MURFIN DRLG. CO.
Farm- Schulze No. 1

SEC. 24 T. 2 R. 24W
C SW SE

Total Depth. 3725'
Comm. 11-30-61 Comp. 12-7-61
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 3-3-62

County Norton
KANSAS



CASING:
8 5/8" 216' cem w/175 sx.

Elevation. 2431' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface soil - sand	195
shale	216
shale-sand	1750
red bed	1993
Anhydrite	2020
shale, sand	2145
shale-shells	2475
shale-lime	2560
sand, lime & shale	2760
lime, shale	3050
shale, lime	3305
lime	3435
lime & shale	3490
lime	3705
Granite Wash & Granite	3725
Total Depth	

TOPS: ELECTRIC	
Anhydrite	1996
Heebner	3406
Toronto	3440
Lansing-Kansas City	3452
Base Kansas City	3640
Granite Wash	3690
Precambrian	3713

DST #1 3405-3465', op 1 hr, rec. 5' mud.
IF 0#, FF 0#, ISIP 580#/30 min. FSIP 200#/30 min.

DST #2 3467-3490', op 1 hr, rec. 30' mud.
IF 0#, FF 10#, ISIP 1020#/30 min. FSIP
770#/30 min.

DST #3 3490-3545', op 1 hr, rec. 50'
mud w/trace of oil. IF 40#, FF 40#,
ISIP 710#/30 min. FBHP 380#/30 min.