

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

State Geological Survey
WICHITA, BRANCH

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 29 T. 2S R. 24 W
Loc. 150' W/C SE NW
County Norton

API No. 15 — 137 — 20,185
County Number

Operator

Hummon Corporation

Address

400 One Main Place, Wichita, KS 67202

Well No.

#2

Lease Name

Wegener

Footage Location

330 feet from 1881 (S) line 810 feet from (E) 2002 line

Principal Contractor

Red Tiger Drilling Company

Geologist

Steve Miller

Spud Date

8-4-80

Date Completed

9-29-80


Total Depth

3785

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser



Elev.: Gr. 2470

DF 2472 KB 2475

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	28#	272	Common	180	2% gel 3%cc
Prod.		4 1/2"	9 1/2#	1857	Halco-Lite	300	10# Gilsonite
					60-40 Poz.	100	3/4 of 1% CFR2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			Two	link jets	1665-1715
TUBING RECORD					
Size Duo line	Setting depth	Packer set at			
2-3/8"	1549'	1549			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Hummon Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: SWDW	
Well No. #2	Lease Name Wegener		
S <u>29</u> T <u>2S</u> R <u>24</u> ^W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
<u>DST #1: 3154-81</u> OP 30-45-45-60 Rec. 30' mud FP 117-227 240' SOSMW SIP 1143-1127			<u>ELECT. LOG</u> Heebner 3410-935 Toronto 3440 -965 Lansing 3456 -981 B/KC 3646 -1171 Gorham 3710 -1235 Reagan 3736 -1261 Gran Wash 3738 -1263
<u>DST #2: 3422-3450</u> OP 30-30-30-30 FP 39-39 Rec. 5' mud w/ few specks oil SIP 70-149			
<u>DST #3: 3468-3506</u> OP 30-30-30-30 FP 47-47 Rec. 20' OCM SIP 172-157			
<u>DST #4: 3505-46</u> OP 30-30-30-30 FP 55 Rec. 20' M w/ few spots oil SIP 721-628			
<u>DST #5: 3637-57</u> OP 30-30-30-30 FP 47-47 REC. 20' Mud SIP 964-839			
<u>DST #6: 3695-3726</u> OP 30-30-30-30 FP 55-55 Rec. 20' mud w/ spots oil SIP 550-416			
<u>DST #7: 3723-3740</u> OP 30-30-30-30 FP 23-23 Rec. 15' mud w/ show free oil SIP 62-39			
<u>DST #8: 3722-3748</u> OP 30-30-30-30 FP 47-70 Rec. 30' mud w/ show oil SIP 110-125			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Wilber Berg Title October 8, 1980 Date		

29-2-24W
State Geological Survey
WICHITA, KANSAS

DRILLERS LOG

No. 2 Wegener

CASING RECORD: COMPANY: Hummon Corporation
8 5/8" @ 272' CONTRACTOR: Red Tiger Drilling Company
w/180 sx cement
4 1/2" @ 1,857' COMMENCED: August 6, 1980
w/400 sx cement COMPLETED: August 18, 1980
TOTAL DEPTH: 3,785'

DESCRIPTION
150' W of C SE/4 NW/4
Sec. 29-T2S-R24W
Norton County, Kansas

ELEVATION: 2,475'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, Sand & Shale	0	280	
Shale	280	930	
Shale & Sand Streaks	930	1663	
Sand	1663	1780	
Shale	1780	2020	
Anhydrite	2020	2049	
Shale	2049	2068	
Shale & Lime Streaks	2068	2290	
Sh & Lime	2290	2555	
Shale	2555	2730	
Shale & Lime Streaks	2730	2850	
Shale & Lime	2850	2950	
Lime	2950	3785	
RTD		3785	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1980
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 28th day of August, 1980.



Jimmie L. Farrice
Notary Public