


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

1-2-25.2

Company- READING & BATES OFFSHORE DRILLING CO. SEC. 1 T. 2 R. 25W
Farm- Lecount No. 1 C SE NW

Total Depth. 3710'
Comm. 12-9-62 Comp. 12-16-62
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 2-23-63

County Norton
KANSAS



CASING:
8 5/8" 285' cem w/200 ex.

Elevation. 2477' KB

Production. DRY

Figures Indicate Bottom of Formations.

shale	120
sand	270
shale	285
clay & shale	1180
sand & shale	1610
shale, sand & pyrite	1988
anhydrite	2020
shale & sand	2274
shale	2400
sand & shale	2925
shale & lime	3000
lime & shale	3180
lime	3496
lime & shale	3573
lime	3650
lime & shale	3705
granite wash	3710 RTD
Total Depth	

TOPS: LOG	
Fort Hayes	510
Dakota	940
Stone Corral	1990 - 2030
Severy Sand	3210
Topeka	3238
Heebner Shale	3349
Snyder Shale	3358
Toronto Lime	3382
Lansing-Kansas City	3392
Base Kansas City	3588
Basal Sand	3654
Granite Wash	3688
Pre-Cambrian Granite	3701'

DST #1 3539-3573' Op 1 hr. Shut in 30 min. Rec. 5' mud.