

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


Company- BROOKS HALL & STRAIN DRILLING
Farm- Odle No. 1

SEC. 14 T. 2 R. 26W
NW NW SE

14-2-26W

Total Depth. 3833
Comm. 4-5-52 Comp. 4-16-52
Shot or Treated.
Contractor.
Issued. 8-23-52

County Decatur
KANSAS



CASING:
8 5/8" 169' cem w/100 sx

Elevation. 2538
2508 (2nd.)
Production. dry

Figures Indicate Bottom of Formations.

soil	50
sand	120
lime sandy	170
shale	600
shale, shells, sand	1365
shale, shells, pyrite	1480
shale	1600
shale, red rock	1700
sand	1770
shale, sand	1800
shale, shells	1925
shale, red rock	2025
anhydrite	2065
shale, shells	2435
lime, shale	2520
shale, shells	2695
lime, shale, pyrite	2815
lime	2870
lime, pyrite	2930
shale, lime	3190
lime	3280
lime, shale	3360
lime	3505
lime, shale	3575
lime	3625
lime, shale	3723
shale red, lime	3742
arbuckle	3765
granite wash	3783
granite	3825
granite wash	3833
Total Depth	

Arbuckle	3742
Granite Wash	3783
Granite	3831

D.S.T. Tool open 1 hr. Rec.
55' drilling mud. BHP 1100#.

Tops:	
Anhydrite	2025
Topeka	3190
Howard	3140
Heebner	3290
Toronto	3319
Lansing	3333
Base Kansas City	3546