

Long Simpson #2-22

1700 FSL 1210 FWL

Sec. 22-2S-27W

Decatur County, Kansas

DST #1 3555-73 (Pollnow) 30-60-60-90; IF: wk bl to 7"; Rec. 2' FO 130' MSW; HP: 1807-1706; FP: 27/43, 44/77; SIP: 1093-1065.

DST #2 3572-97 (27') 30-60-60-90; IF: wk to 6", had to reset. Rec. 2' CO, 210' MW (20% M), 125,000 ppm. cl.; HP: 1808-1743; SIP: 1095-1082; FP: 67/88, 91/123, BHT 102°.

DST #3 3593-3640 (47'), 30-60-60-90, IF: wk bl throughout; FF: wk bl inc to 5" @ end; Rec. 130' OCM (15% oil) no wtr; HP: 1825-1778; FP: 20/44, 41/55; SIP: 675-530; BHT 100°.

DST #4 3630-3659 30-30-30-30; IF: wk sur bl throughout. FF: no blow. Rec. 5' M; HP: 1861-1792; FP: 19/29, 27/36; SIP: 918-798; BHT 97°.

DST #5 3658-3719 30-30-30-30; IF: wk sur bl, died in 20 min. FF: no bl.; Rec. 5' M; HP: 1867-1834; FP: 21/27, 27/37; SIP: 292-145; BHT 100°.