

P1



11111
15-2-27W
State Corporation Commission
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: Baird Oil Company, Inc
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SIMPSON #1
 LOCATION: C NE SW, Section 15-2S-27W
 Decatur County, Kansas
 SPUD DATE: 09-22-80
 COMPLETION DATE: 09-30-80

| | | |
|------|------|--------------------|
| 0 | 217 | Sand & Shale |
| 217 | 2126 | Shale & Sand |
| 2126 | 2158 | Anhydrite |
| 2158 | 2295 | Shale |
| 2295 | 2995 | Shale & Sand |
| 2995 | 3488 | Lime & Shale |
| 3488 | 3720 | Lime |
| | 3720 | Rotary Total Depth |

Spud hole @ 4:30 p.m. 09-22-80. Drilled 217' of a 12-1/4" hole. Ran 5 joints of 8-5/8" 20# casing (tally 208.31') Set @ 216'. Cemented with 175 sx. of Class A cement, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 8:45 p.m. 09-22-80.

T.D. 3720'. Ran 91 joints of 4-1/2" 9-1/2# casing (tally 3743' overall) Set @ 3718'. Cemented with 35 sx. of 50/50 posmix, 12-1/2# gilsinite per sx. Followed with 200 sx. of Class A, 2% gel, 18% salt, .75% CFR2 per sx. Plug was down @ 2:45 p.m. 09-30-80.

SAMPLE TOPS:
 Anhydrite 2126'
 B/Anhydrite 2158'

RECEIVED
 STATE CORPORATION COMMISSION
 OCT - 8 1980
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SIMPSON #1, C NE SW, Section 15-2S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
 Jack L. Partridge - Asst. Sec. Treas.