

WICHITA BRANCH


KANSAS DRILLERS LOG

S. 16 T. 2S R. 28 **EW**

Loc. \_\_\_\_\_

County Decatur

640 Acres  
N



Sec.: Gr. 2589

DF \_\_\_\_\_ KB 2593

API No. 15 — Decatur — 039-20466  
County Number

Operator  
Hansen Trust

Address  
Box 185 Logan, KS

Well No. #1 Lease Name Kreymborg

Footage Location  
660 feet from **(N)** (S) line 660 feet from **(E)** (W) line

Principal Contractor J & C Drilling Co., Inc. Geologist Jim Reeves

Spud Date August 29, 1979 Total Depth 4132' P.B.T.D. \_\_\_\_\_

Date Completed September 9, 1979 Oil Purchaser \_\_\_\_\_

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24 Lb.	187	50/50Pos. Mix	150	2% Gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____	CFPB _____
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 New Address (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

245 North Water  
Wichita, Kansas 67202

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator

Well No. #1 Lease Name Kreymborg Dry Hole

S 16 T 2 S R 28 E W

**WELL LOG**

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MANNERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	10		
Shale	10	370		
Limey Shale	370	410	Niobrara	370
Shale	410	770		
Lime	770	820		
Lime & Shale	820	1165		
Sand & Shale	1165	2050	Dakota	1165
Shale	2050	2245		
Anhydrite	2245	2280	Stone Coral	2245
Shale & Lime	2280	2900		
Lime & Shale	2900	3390		
Lime	3390	3440	Topeka	3390
Lime & Shale	3440	3550		
Lime & Shells with Shale	3550	3760	Lansing	3550
Shale & Lime	3760	3880		
Shale & Sand	3880	4070		
Dolomite	4070	4120	Arbuckle	4070
Pink Granite	4120	4132	Granite	4120
DST #1 3502-3610 30''-45''-30''-45'' IFP 224-295, FFP 326-408, FSIP 1248, FSIP 1218				
Rec. 330' Mud with few oil spots, 615' Watery Mud				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature
	Title
	Date