

State Geological Survey
WICHITA, BRANCH

WELL LOG

15-039-20474
23-2-28W

COMPANY Murfin Drilling Company

FARM RUSH

NO. 3

SEC. 23 T. 2S R28W
LOC.

C NE NW

RIG. NO. 7

TOTAL DEPTH

COMM.

3720'

COMP.


11-18-79

CONTRACTOR

Murfin Drilling Company

Decatur
COUNTY

KANSAS



CASING

20
15
12
13

10

8 -5/8" csg. set @ 174' w/150 sx. of
6 60-40 posmix, 3% Sunset.

ELEVATION

2534' K.B.

2529' G.L.

PRODUCTION

4 1/2" csg. set @ 3713' w/175 sx. (25 sx. of Class A + 75 sx. of 50-50 posmix,

FIGURES INDICATE BOTTOM OF FORMATIONS

2% gel, 10% salt, 3/4% CFR-2 + 75 sx. of 50-50 posmix, 10% salt, 2% gel, 3/4% CFR-2, 70 gallons of Latex)

65'	Top soil & Sand
174'	Blue Shale
625'	Shale
1545'	Shale & Lime
1970'	Shale & Sand
2166'	Shale
2201'	ANHYDRITE
3115'	Shale & Lime
3640'	Lime & Shale
3655'	Shale & Lime
3720'	Lime & Shale