

Operator PICKRELL DRILLING COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE

Well No. 1 Lease Name EUHUS "A"

S 28 T 2S R 28W E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Soil	0	30	DST #1 3464-3496, 30-30-90-60	
Shale	30	221	Rec. 325' wtr/spks oil, IFP	
Shale	221	1050	17-52# FFP 52-157# ISIP	
Shale	1050	1800	1289# FSIP 1254#	
Shale & Sand	1800	1972	DST #2 3494-3525, 30-30-60	
Sand	1973	2031	Gd. blow. Rec. 260' wtr/scum	
Shale	2032	2225	oil, IFP 27-53# FFP 63-144#	
Shale	2225	2260	ISIP 1185# FSIP 1167#	
Shale & Lime	2260	2510	DST #3 - Misrun	
Shale & Lime	2510	2755		
Shale & Lime	2755	2960	DST #4 3534-3544, 30-30-60-90	
Lime & Shale	2960	3110	Good blow, Rec. 5' oil, 945'	
Shale & Lime	3110	3225	wtr. IFP 44-235# FFP 244-452#	
Shale & Lime	3225	3390	ISIP 1324# FSIP 1324#	
Lime & Shale	3390	3496		
Lime & Shale	3496	3526	DST #5 3542-3573, 30-30-90-60	
Lime & Shale	3526	3544	Good blow. Rec. 505' wtr. show	
Shale	3544	3562	free oil on top. IFP 27-90#	
Lime	3562	3573	FFP 99-269# ISIP 1365# FSIP	
Lime	3573	3620	1356#	
Lime	3620	3627	DST #6 3577-3627, 30-30-10-Out	
Lime	3627	3715	Wk. blow died. Rec. 20' mud	
Lime & Shale	3715	3725	IFP 36-45# ISIP 90#	
Shale	3725	3745	DST #7 3622-3715, 30-30-60	
			Wk. blow died. Rec. 75' mud	
			FP 54-72# SIP 323#	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

C. W. Sebitts
 C. W. Sebitts
 Partner
 Signature
 Title
 6-1-79
 Date