

33-3-28W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Rehm No. 1

SEC. 33 T. 2 R. 28W
 NE NE NW

Total Depth. 3730'
Comm. 10-7-59 Comp. 10-16-59
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 12-26-59

County Decatur
 KANSAS



CASING:

8 5/8" 197' cem.
4 1/2" 3723' cem.

Elevation. 2534' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand & clay	70
shale	1545
sand & shale	1700
shale	1905
shale, sand & shells	2220
Anhydrite	2255
shale	2410
shale & lime	2675
lime	2840
shale & lime	2945
lime	3145
lime & shale	3270
lime	3610
shale & lime	3730 RTD
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Topeka	3317	3316
Heebner	3482	3482
Toronto	3511	3511
Lansing	3524	3521
Pollnow	3549	
Base Kansas City	3722	3819

DST #1 3547' tool plugged, Misrun.

DST #2 3545', op 40 min. SI 90 min.
rec. 210 cc oil, 7 cc fmtn. wtr. 113 cc
filtract wtr. BHP 470#, incr.

DST #3 3563½' op 40 min. SI 75 min.
rec. 55 cc oil, 7 cc fmtn. wtr. &
150 cc filtrate wtr. No BHP.

DST #4 3666', op 40 min. SI 30 min.
rec. scum of oil, 795 cc fmtn., 2385 cc
filtrate wtr. BHP 1355#.