

29-2-29W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY BURCH EXPLORATION, INC.

SEC. 29 T. 2 R. 29W
LOC. SW SW SW

FARM Shaw "A" NO. 1

TOTAL DEPTH 4010

COMM. 12-16-66


COMP. 12-24-66

SHOT OR TREATED

CONTRACTOR Abercrombie Drlg.

ISSUED 3-18-67

COUNTY Decatur



CASING

20 10
15 7" @ 223' w/100 SX
12 6
13 4 1/2" @ 4009' w/100 SX

ELEVATION 2767' KB

PRODUCTION ST TST: 30 BOPD
TR WTR, Grav 39, KC 3814-15

FIGURES INDICATE BOTTOM OF FORMATIONS

Set 7" surface casing at 223 feet with 100 sacks of cement.

Set 4-1/2" production casing at 4009 feet with 100 sacks of cement.

0	151	Clay
151	195	Sand
195	1588	Shale
1588	2018	Sand
2018	2258	Shale
2258	2273	Anhydrite
2273	2513	Shale (Red)
2513	2545	Anhydrite
2545	2715	Shale
2715	3065	Lime & Shale
3065	3358	Shale & Lime
3358	4010	Lime & Shale
	4010	Total Depth

Elevation: 2767 K.B.
2760 G.L.

Formation Tops:

Heebner	3737	(- 970)
Toronto	3768	(-1001)
Lansing	3781	(-1014)
B/K.C.	4007	(-1240)
Total Depth	4010	(-1243)

TOPS: SAMPLE

Blaine Anhydrite	2258
B/Blaine	2275
B/Anhydrite	2545
Heebner	3737
Toronto	3768
Lansing	3781

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS