

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

14-2-30W

COMPANY HALLIBURTON OIL PRODUCING


SEC. 14 T. 2 N. 30W
 LOC. C SE SW

FARM Jording "B" NO. 1

TOTAL DEPTH 4030
 COMM. 1-24-67 COMP. 2-1-67
 SHOT OR TREATED
 CONTRACTOR Paine Drlg.
 ISSUED 4-15-67

COUNTY Decatur

KANSAS



CASING

20 10
 15 7" @ 320' w/150 sx
 12 6
 13 4 1/2" @ 4022' w/125 sx

ELEVATION 2838'KB

PRODUCTION PMP 71 BOPD
 & 16 % Wtr., GRAV 33
 LANS 3851-3978

FIGURES INDICATE BOTTOM OF FORMATIONS

0	322	Surface Sand & Shale
322	515	Shale
515	1420	Shale & Sand
1420	2345	Shale
2345	2574	Red Bed
2574	2607	Anhydrite
2607	2645	Shale
2645	2870	Shale & Shells
2870	3199	Shale & Lime
3190	3822	Lime & Shale
3822	3955	Lime
3955	4030	Lime & Shale
4030		Rotary Total Depth

TOPS: SCOUT

Anhydrite	2570
Base Anhydrite	2600
Howard	3543
Severy sand	3633
Topeka	3659
Heebner	3771
Lansing	3818

Set 7-inch Surface Casing @ 320 ft. with 150 sx cement.

Set 4-1/2-inch Production Casing @ 4022 ft. with 125 sx cement.

We hereby certify that the above is a correct and accurate log of the above mentioned well, as shown on the daily drilling reports.

PAINE DRILLING CO., INC.

BY: *D. F. McCarthy*

Subscribed and sworn to before me this 3rd day of February, 1967.

Lora Queller
 Notary Public