

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

14-2-30W

COMPANY HALLIBURTON OIL

SEC. 14 T. 2 R. 30W

FARM Mines

NO. 2

LOC.

NW SW NE

TOTAL DEPTH 4025'

COMM. 11-22-67

COMP. 11-30-67

SHOT OR TREATED


CONTRACTOR Leben Drlg.

ISSUED 2-10-68

COUNTY

Decatur

KANSAS



CASING

20

10

15

8 5/8" 330' cem w/ 225 sx

ELEVATION

2813' KB

12

6

13

5

PRODUCTION

96 BOPD PLUS WTR

4 1/2" 4025' cem w/ 225 sx

(Lans 3949-56)

FIGURES INDICATE BOTTOM OF FORMATIONS

0	60	Surface Clay
60	330	Shale, Sand
1970	1970	Shale
1970	2210	Shale, Sand, Shale
2210	2549	Shale, Sand
2549	2584	Anhydrite
2584	3340	Shale, Lime
3340	3452	Lime
3452	3575	Lime, Shale
3575	3745	Shale, Lime
3745	4025	Lime
	4025	RTD - Set 4 1/2" Casing


TOPS: LOG

Anhydrite (s) 2549

Base Anhydrite (s) 2584

Heebner 3749

Lansing 3795



8 5/8" 8 rd. 20# new surface casing set @ 330' cemented with 225 sacks
Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mines #2 Well, located NW SW NE of Section 14, Township 2 South, Range 30 West, Decatur County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 30th day of November, 1967.

Wanda D. Duffield