

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


14-2-30w

COMPANY HALLIBURTON OIL PRODUCING
FARM Jording "B" NO. 2

SEC. 14 T. 2 R. 30W
LOC. SE NE SW

TOTAL DEPTH 4025'
COMM. 3-29-67 COMP. 4-7-67
SHOT OR TREATED
CONTRACTOR Paine Drilling
ISSUED 6-3-67

COUNTY Decatur



CASING
20 10
15 8x8x7" 318' cem w/ 150 sx
12 6
13 5
4 1/2" 4024' cem w/ 125 sx

ELEVATION 2784' KB

PRODUCTION 97 BOPD,
LKC 3920-24, GR .35

FIGURES INDICATE BOTTOM OF FORMATIONS

0	318	Surface Sand & Shale
318	770	Shale
770	1490	Shale & Sand
1490	1760	Shale
1760	2460	Shale & Pyrite
2460	2516	Red Bed
2516	2549	Anhydrite
2549	2900	Shale
2900	3256	Shale & Lime
3256	3420	Shale & Pyrite
3420	3800	Lime & Shale
3800	3900	Lime
3900	4025	Lime & Shale
4025		Rotary Total Depth

Top : Scout
Topeka 3601
Heebner 3716
Ransing 3767

CONFIDENTIAL DIVISION
WICHITA, KANSAS

Set 7-inch Surface Casing @ 318 ft. with 150 sx cement.

Set 4-1/2 inch Production Casing @ 4024 ft. with 125 sx cement.

We hereby certify that the above is a correct and accurate log of the above mentioned well, as shown on the daily drilling reports.

PAINE DRILLING CO., INC.

BY: D. F. McCarty
Treasurer

Subscribed and sworn to before me this 17th day of April, 1967.

Carroll D. Baker
Notary Public