

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

23-2-30W


COMPANY **HALLIBURTON OIL**

SEC. 23 T. 2 R. 30W
 LOC. 150' W of C NW NE

FARM **Jording "A"** NO. **1**

TOTAL DEPTH **4035'**
 COMM. **1-12-67** COMP. **1-21-67**
 SHOT OR TREATED
 CONTRACTOR **Paine Drig.**
 ISSUED **2-25-67**

COUNTY **Decatur**



CASING
 20 10
 15 ~~7"~~ 309' cem w/ 160 sx
 12 6
 13 5

ELEVATION **2832' KB**

PRODUCTION **DRY/ Kansas City**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	311	Surface Sand & Shale	TOPS: SCOUT	
311	600	Shale	Anhydrite	2576
600	1485	Shale & Sand	Base Anhydrite	2608
1485	1890	Shale	Topeka	3620
1890	2190	Shale & Shells	Heebner	3778
2190	2572	Shale & Red Bed	Lansing	3822
2572	2604	Anhydrite		
2604	2810	Shale & Red Bed		
2810	3230	Shale		
3230	3830	Lime & shale		
3830	4035	Lime		
4035		Rotary Total Depth		

Set 7-inch Surface Casing @ 309 feet with 160 sx cement.

Dry & Abandoned

We hereby certify that the above is a correct and accurate log of the above mentioned well, as shown on the daily drilling reports.

PAINE DRILLING CO., INC.

BY: *D. F. M. Leatty*
 Treasurer

Subscribed and sworn to before me this 23rd day of January, 1967

Donald Low
 Notary Public