

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

35-2-30W

COMPANY ABERCROMBIE DRILLING

SEC. 35 T. 2 R. 30W
LOC. NE SE NE

FARM Berndt

NO. 1

TOTAL DEPTH 4077'

COMM. 6-19-68

COMP. 8-8-68


SHOT OR TREATED

CONTRACTOR Abercrombie Drilling

ISSUED 9-14-68

COUNTY Decatur

KANSAS



CASING

20

10

15

8 5/8"

12

XX 7" 247' cem w/ 75 sx

13

5

4 1/2" 4076' cem/ 150 sx

ELEVATION 2812' KB

PRODUCTION P 155 BOPD, NW

Grav 34/ Lans 3868-72, 3834-40

FIGURES INDICATE BOTTOM OF FORMATIONS

0	40	Lime
40	200	Rock w/Sand
200	1390	Shale
1390	1862	Sand & Shale
1862	2240	Shale w/Gyp Streaks
2240	2576	Shale
2576	2609	Anhydrite
2609	2755	Shale
2755	3050	Shale w/Sand Streaks & Lime
3050	3873	Lime & Shale
3873	3892	Lime
3892	4077	Lime
	4077	R. T. D.

Drilled 250' of 9" hole & set 7" csg. @247' w/75 sx. Sunset cement.

Plug was down 6-19-68.

Set 4 1/2", 10 1/2" csg. @4076' w/150 sx. 50/50 Posmix cement.

SAMPLE FORMATION TOPS

ELEVATION

T/Anhydrite	2576	(+ 236)	2812 K. B.
Heebner	3785	(- 973)	2810 D. F.
Toronto	3819	(-1007)	2804 G. L.
Lansing	3835	(-1023)	

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Berndt #1, NE SE NE, Sec. 35-2S-30W, Decatur County, Kansas.

A. L. Abercrombie
A. L. Abercrombie, President