

23-2-30W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- HALLIBURTON OIL PRODUCING CO.
 Farm- May No. 1

SEC. 23 T. 2 R. 30W
 E NW SW

Total Depth. 4090'
 Comm. 12-30-62 Comp. 1-9-63
 Shot or Treated.
 Contractor. Burch Drlg.
 Issued. 4-6-63

County Decatur
 KANSAS



CASING:
 8 5/8" 288' cem w/225 sx.

Elevation. 2856' KB

Production. Dry

Figures Indicate Bottom of Formations.

shale	1965
lime & shale	2300
Blaine Anhydrite	2326
shale	2597
Cimmarron Anhydrite	2632
lime & shale	2662
lime & sand	2840
lime & shale	3154
lime & sand	3243
lime & shale	3651
lime & sand	3754
lime & shale	3855
lime	3875
lime & shale	4000
lime	4090 RTD
Total Depth	

TOPS: LOG	
Anhydrite	2599
Howard	3571
Severy	3659
Topeka	3683
Heebner	3796
Lansing	3844
Base Kansas City	4064

DST #1 3797-3855', op 40 mins, Rec. 30'
 mud. IBHP 140#, IFP 10#, FFP 20#,
 FBHP 60#.

DST #2 3968-4000', op 1 hr, Rec. 2' oil,
 12' slightly oil cut mud. IBHP 480#,
 IFP 10#, FFP 20#, FBHP 70#.