

WICHITA BRANCH
KANSAS DRILLERS' LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-153-20297

18-2-33W

API No. 15 — 153 — 20,297
County Number

Operator

Edward J. Ackman

Address

811 Denver Center Bldg. Denver, Colorado

Well No.

#1

Lease Name

Rosie Reuber

Footage Location

1980' feet from (X) (S) line 1980 feet from (E) (XX) line

Principal Contractor

Stoepelwerth Drilling

Geologist

Allen Hallock

Spud Date

Sept. 2, 1977

Total Depth

4323'

P.B.T.D.

Date Completed

Sept. 10, 1977

Oil Purchaser


S. 18 T. 2S R. 33 W

Loc. C-NW-SE

County Rawlins

640 Acres

N



Locate well correctly

Elev.: Gr. 3076

DF KB 3081

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	24#	230	Pozmix	115	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Cement Plugs: 1200' 70 sacks	
240' 20 sacks	
40' 10 sacks	
50/50 Pozmix, 6% Gel.	


INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:																			
Well No. 1	Lease Name Rosie Reuber	Dry Hole																			
S <u>18</u> T <u>2S</u> R <u>33</u> ^K _W Rawling County																					
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.																			
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.																					
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%; padding: 5px;">NAME</th> <th style="width: 40%; padding: 5px;">DEPTH</th> </tr> </thead> <tbody> <tr><td style="padding: 5px;">Stone Corral</td><td style="text-align: right; padding: 5px;">2875</td></tr> <tr><td style="padding: 5px;">Foraker</td><td style="text-align: right; padding: 5px;">3567</td></tr> <tr><td style="padding: 5px;">Topeka</td><td style="text-align: right; padding: 5px;">3861</td></tr> <tr><td style="padding: 5px;">Oread</td><td style="text-align: right; padding: 5px;">3963</td></tr> <tr><td style="padding: 5px;">Lansing</td><td style="text-align: right; padding: 5px;">4020</td></tr> <tr><td style="padding: 5px;">Base Kansas</td><td></td></tr> <tr><td style="padding: 5px;">City</td><td style="text-align: right; padding: 5px;">4287</td></tr> <tr><td style="padding: 5px;">Total Depth</td><td style="text-align: right; padding: 5px;">4323</td></tr> </tbody> </table>	NAME	DEPTH	Stone Corral	2875	Foraker	3567	Topeka	3861	Oread	3963	Lansing	4020	Base Kansas		City	4287	Total Depth	4323
NAME	DEPTH																				
Stone Corral	2875																				
Foraker	3567																				
Topeka	3861																				
Oread	3963																				
Lansing	4020																				
Base Kansas																					
City	4287																				
Total Depth	4323																				
Ran Great Guns Log Gamma Ray-Neutron-Guard Drill Stem Test No. 1 4077-4323 30"-60"-60"-60" Recovered: 122' Mud 386' S.O.C. Salty Mud 580' S.O.C.S.W. IHP 2293 1st IF/FFP 183/456 ISIP 1463 2nd IF/FFP 475/712 FSIP 1443 FHP 2275																					
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.																					
Date Received	 Edward J. Ackman Operator																				
	Signature Title September 19, 1977 Date																				

297762